



Data Center Facilities for Smart Buildings


“How modern data centers support smart infrastructure”

“Building Towards Sustainable Growth”

Presented By : Phyo Thet Zin

Data Center Design & Solution

Data Center : The Foundation of every organization



- Having high-performance ICT (Information and Communication Technology) resources on hand is essential for business processes to achieve corporate goals.

Types of Data Center

❖ Enterprise Data Center

- ❖ Owned and operated by a single organization for internal use

❖ Colocation Data Center

- ❖ Facilities where multiple organizations rent space and resources

❖ Cloud Data Centers

- ❖ Hosted by cloud service providers like AWS, Google Cloud, and Microsoft Azure

❖ Edge Data Centers

- ❖ Smaller facilities located close to users for low-latency processing

Data Center Standards

**Data Center are classified (Tier 1 to Tier 4) based on uptime and redundancy
Optimizing power usage through renewable energy, efficient cooling, and
power management (PUE – Power Usage Effectiveness)**

- ❖ Physical Security – Surveillance, biometric access, and controlled entry**
- ❖ Physical Security – Surveillance, biometric access, and controlled entry**
- ❖ Disaster Recovery – Backup strategies, failover systems, and redundancy**

Data Center Standards

❖ **Rated-1 Data Center; Basic**

- ❖ Single path for power and cooling without redundancy
- ❖ Many single points of failure

❖ **Rated-2 Data Center; Redundant Components**

- ❖ Single path for power and cooling with component redundancy i.e. **N+1**

❖ **Rated-3 Data Center; Concurrently Maintainable**

- ❖ Multiple path for power and cooling of which one is active allowing maintenance or testing on one path without causing interruption to the critical load


❖ **Rated-4 Data Center; Fault Tolerant**

- ❖ Multiple active paths for power and cooling with redundancy in each path.
- ❖ Allows for one fault.

Data Center Standards

	TIER I	TIER II	TIER III	TIER IV
Number of delivery paths	Only 1	Only 1	1 active 1 passive	2 active
Redundant components	N	N+1	N+1	2 (N+1) or S+S
Support space to raised floor ratio	20%	30%	80-90%	100%
Initial watts/ft ²	20-30	40-50	40-60	50-80
Ultimate watts/ft ²	20-30	40-50	100-150	150+
Raised floor height	12"	18"	30-36"	30-36"
Floor loading pounds/ft ²	85	100	150	150+
Utility voltage	208, 480	208, 480	12-15kV	12-15kV
Months to implement	3	3 to 6	15 to 20	15 to 20
Year first deployed	1965	1970	1985	1995
Construction \$/ft ² raised floor*	\$450	\$600	\$900	\$1,100+
Annual IT downtime due to site	28.8 hrs	22.0 hrs	1.6 hrs	0.4 hrs
Site availability	99.671%	99.749%	99.982%	99.995%

Data Center : Risk Factors





Predominant causes of Data Center Failures

- ❖ Human Error**
- ❖ Power Quality Issue**
- ❖ Electro Magnetic Fields (EMF)**
- ❖ Environmental Conditions**

Predominant causes of Data Center Failures

❖ Human Error

- ❖ No or poorly executed processes and work instructions
- ❖ Unauthorized access
- ❖ Accidents
- ❖ Unnoticed Alarm

❖ Power Quality Issue

- ❖ Poor Voltage/ Current/ Frequency regulation
- ❖ High level of Common and Normal mode noise
- ❖ High ground resistance
- ❖ Harmonics



Predominant causes of Data Center Failures

❖ Electro Magnetic Fields (EMF)

- ❖ High radiation levels from power cables/ UPS/ Transformers/ PDU/ Lighting etc.

❖ Environmental Conditions

- ❖ Temperature/ Humidity
- ❖ Wrong cooling principles
- ❖ High levels of contamination

Data Center; Location, Building and Construction

❖ Site selection is difficult

- ❖ Technical requirements evaluation
- ❖ Decision making process/ Business evaluation

❖ Technical evaluation

- ❖ Often done by engineers
- ❖ Want the best to meet design criteria

❖ Business evaluation

- ❖ Done by senior management
- ❖ Return On Investment (ROI)/ cost
- ❖ Prestige
- ❖ Location


Data Center; Location, Building and Construction

❖ Potential natural hazards


- ❖ Lightning
- ❖ Flooding
- ❖ Typhoon
- ❖ Forest Fires
- ❖ Seismic activity (Earthquake)

❖ Potential man-made hazards

- ❖ Flight Path
- ❖ Tunnels, Lake,
- ❖ Train/ Airport, RF Tower
- ❖ Power distribution network
- ❖ Industrial pollution, Etc.



Data Center; Location, Building and Construction



Data Center; Location, Building and Construction

Holding area

- Purpose
 - Aimed at providing an area where goods can be received, unpacked, physically inspected, and prepared for movement into the staging area
- Requirements
 - Easy access for external supply (i.e. loading bay and route to staging area)
 - Spacious
 - Proper garbage disposal
 - Secure

Data Center; Location, Building and Construction

Staging area

- Purpose
 - Provides an area where equipment can be acclimated, inspected, configured (H/W & S/W) and safely tested to ensure deployment readiness
- Requirements
 - Separate and secure space
 - Separate network if possible/needed
 - Separate PDU (Power Distribution Unit)
 - Environmentally controlled and monitored
 - Fire protection and other safety measures



Data Center; Location, Building and Construction

Computer/Server room

- Purpose
 - Provides a safe production environment where equipment can be expected to run on a 24x7 basis with minimal risk of interruption
- Requirements
 - Separate and highly secure space
 - Protection and control of power quality
 - Environmentally controlled and monitored
 - Low EMF (Electro Magnetic Field) radiation levels
 - Fire protection and other safety measures



Data Center; Location, Building and Construction

Media storage area

- Purpose
 - Provides a safe, secure and conditioned environment where media (documentation, tapes, cd-rom's etc.) can be stored in a controlled manner
- Requirements
 - Separate and secure space
 - Environmental controlled and monitored
 - Fire protection and other safety measures
 - Preferably highly sensitive smoke detection systems
 - Shelter/Bunker

Data Center; Location, Building and Construction

UPS room


- Purpose
 - Provides a safe, secure and conditioned environment where Power Protection and Conditioning systems can operate on a 24x7 basis
- Requirements
 - Separate and secure space
 - Environmental controlled and monitored
 - Fire protection and other safety measures
- Note: in some cases a small rating UPS could be located within the computer room



Data Center; Location, Building and Construction

Battery room

- Purpose
 - Provides a safe, secure and conditioned environment where batteries can be stored
- Requirements
 - Separate and secure space
 - Ideally separated from UPS room
 - Environmental controlled and monitored
 - Fire protection and other safety measures
 - Vented; if needed/required



Data Center; Location, Building and Construction

Service corridor

- Purpose
 - Provides a secure area where supporting facilities can be serviced and monitored on a 24 x 7 basis without disturbing the data centre
- Requirements
 - Separate and secure space
 - Environmental controlled and monitored
 - Fire protection and other safety measures



Data Center; Location, Building and Construction

Standby generator set room/area


- Purpose
 - Provides a safe and secure area where the standby generator set can be located to allow for safe operation with minimal disturbance
- Requirements
 - Separate and secure area
 - Fire protection and other safety measures
 - Fuel tanks could be located underground or above ground
 - Regulations apply and need to be reviewed before making a decision on which type to use



Data Center; Location, Building and Construction

Meet-Me / Entrance room

- Purpose
 - Provides a safe production environment where the carrier handover point equipment can be expected to run on a 24x7 basis with minimal risk of interruption
 - Note: sometimes located within the data centre
- Requirements
 - Separate and secure space
 - Protection and control of power quality
 - Environmental controlled and monitored
 - Fire protection and other safety measures



Data Center; Location, Building and Construction

Security room

- Purpose
 - Provides a secure area where security functions can be undertaken on a 24 x 7 basis
- Requirements
 - Separate and secure space
 - Protection and control of power quality
 - Fire protection and other safety measures




Data Center; Location, Building and Construction

NOC (Network Operations Control)/Command centre

- Purpose
 - Provides a secure area where the ICT infrastructure and supporting facilities can be monitored and controlled on a 24 x 7 basis
 - Note: sometimes combined with Security room
- Requirements
 - Separate and secure space
 - Protection and control of power quality
 - Environmental controlled and monitored
 - Fire protection and other safety measures




Data Center – Raised Floor System



Data Center – Raised Floor System

- Two types of floors
 - Die formed welded steel construction




- Die formed welded steel shell with cement-filled core




Data Center – Raised Floor System

- Raised floor needs to be connected to the ground wire
- Signal Reference Grid (SRG)
 - Provide an equipotential plane for the equipment contained within computer/server rooms.
 - Provides a low-impedance path for high-frequency noise currents to dissipate before they cause breakdown of equipment




Data Center – Raised Floor System




- All racks must be individually bonded to the SRG.
 - Serial bonding is not allowed
- Ideally created via braided copper wire or flat copper strip connected to every other pedestal or surrounding frame (IEEE-1100)
- Acceptable via grounded raised floor frames
 - Hanging or bolted frame must be free of corrosion



Data Center – Power Source



Data Center Redundant Supply




Data Center – Power Redundancy Source




Data Center – Power Redundancy Source




Data Center – Power Redundancy Source




Data Center – Power Redundancy Source – Low availability




Data Center – Power Redundancy Source – Slightly availability



Data Center – Power Redundancy Source – Improved availability




Data Center – Power Redundancy Source –Improved availability



Data Center – Cooling System

Cooling is very important for data centres and their availability



Sources for Electronic Component Failure

Data Center – Cooling System

Comfort Air Con

- Low sensible heat load capabilities
- Simple thermostat, temperature control
- No humidification and/or de-humidification sections
- Not aimed at 24x7 operations
- Filter sections often not adequate for data centre environments
- Often no proper interface for monitoring and control
 - Fire suppression



Data Center – Cooling System

Precision air conditioners


- High sensible heat load capabilities
- Narrow thresholds for temperature and humidity control
- Contains humidification and dehumidification sections
- Proper filter sections
- Aimed at 24x7 operations and therefore more reliable and robust
- Proper interface for monitoring and control



Data Center – Cooling System


Top Flow

- Can be installed with or without raised floor
- Limited airflow guidance (need to use ducting)




Down Flow

- Can 'only' be used with raised floor
- Allows for air flow guidance through raised floor



Data Center – Cooling System

Raised floor design is based on the principle of an under-floor cold air distribution path, whereby the hot air is flowing back to the air-conditioner unit either via the room or via a dedicated duct or suspended ceiling void.



Data Center – Fire Suppression System

Novec - 1230

- Cost effective installation and maintenance
- Very effective for fire suppression
- Clear gas
- Environmentally safe
- Gas Containers should be reasonably close to data centre
- Containers can be refilled on site



Data Center – Fire Suppression System

EPO (Emergency Power Off)

Auto unlock doors

- Doors should use swing-out principle (code permitted)

Escape routes should be clear and within distance required by law (Automatic) shutdown of Air-conditioners

- country dependent, check regulation

Integration with existing building fire panel

Gas manual release and Gas abort buttons

Check your local fire-codes



Data Center – Security System

Perimeter protection and detection

- Fencing / Walls
- Moat
- Security Guards
- CCTV

CCTV

- Recording on hard disk
- Motion detection cameras
- Night vision camera
- Event/face recognition



Cameras and recorder must be on UPS

Recorder to be located in a secure area

- Avoid placement inside the computer room

Copy of hard disk should be stored off site or in another remote area of the building

Evaluate history requirements and regulations

Data Center – Security System

Doors can be secured in various ways

- Key lock
 - Proper key management procedures
- Electronic locks
 - Card reader
 - Security code
 - Biometrics (fingerprint, iris scan etc.)



Avoid tailgating at doors

- Use revolving doors
- Enforce strict policies
- Sign in/out logs

Review door access logs and security violations on a weekly basis and take action

Data Center – Security System

Ensure only persons allowed enter the computer room and other restricted areas

Supervise visitors where possible or use CCTV

Use 'cages' where possible

- No impact on cooling/fire suppression systems

Secure and lock all:

- Racks
- CRAC
- PDU' s
- Etc.

Proper key management

Enforce policies



Data Center – Monitoring System

Remote monitoring can be achieved through the existing TCP/IP based network by using SNMP or other protocols

